

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for the construction of a Girder Bridge for foundations, piers and abutments across river Shimsha at Halagur 2-55 of Bangalore, Mysore Road, via Kankanhalli, (18' Roadway).

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavating foundations for wells of abutments and piers	C.yd.	0 12 0	652	489
2	Erecting cement concrete curbs 1 : 2 : 4 5'-0" external diameter 4'-6" internal and 3" thick and 1½' high cast in site including frame work and fixing charges, etc., complete.	R.ft.	6 8 0	1,452	9,438
3	Filling hollows of curbs with surki concrete ..	C.ft.	0 5 0	23,203	7,251
4	Compound main girders 26" × 12" × 174.5 lbs. .. Do end girder 23½" × 12" 128 lbs. including hoisting charges and a prime coat of anti-corrosive or any other approved paint	Ton	200 0 0	139.40	27,880
5	Carting girders from Chennapatna Railway Station to Halagur a distance of 15 miles	Ton Mile	1 0 0	2,091	2,091
6	Mild steel bearing plates 36" × 18" × 1" for seating of girders.	Each	7 8 0	52	390
7	Reinforced cement concrete (1 : 2 : 4) decking 8½" thick as per design with necessary expansion joints, etc., complete with 18' roadway (530' × 18½' × 8½")	S.ft.	2 4 0	6,741	15,167
8	Railing with 1½" pipe on angle iron standards 3" × 3" × 3' high etc., complete	R.ft.	2 0 0	1,080	2,160
9	New stone revetment for wings	C.yd.	2 0 0	75	150
10	Pitching 2' deep the bed between the piers ..	C.yd.	2 0 0	569	1,138
11	Retaining wall for pitching	R.ft.	2 4 0	1,080	2,430
12	Ring bund, un-watering and diversion of river ..	L. S.	Rupees	..	2,000
13	Temporary sheds	..	Do	..	500
14	Approach roads	..	Do	..	350
15	Unforeseen charges	L. S.	..	..	866

V. V. PATANKAR,
Executive Engineer.

MEDICAL DEPARTMENT

EPIDEMIC DISEASES HOSPITAL, ROBERTSONPET, KOLAR GOLD FIELDS.

Abstract Notification.

The attention of the public is invited to the tender notification, published in the *Mysore Gazette*, pages 1701 and 1702 of Part VI, dated 15th October 1936, for the supply of diet articles, etc., to the Epidemic Diseases Hospital, Robertsonpet.

The last date for receiving tenders is 25th November 1936.

C. NARAYANA RAO,
Medical Officer (in-charge).